

MODEL : RS-150-5

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 80 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 26 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 4.75 V- 5.5 V	I/P: 230 VAC I/P: 115 VAC O/P:MIN LOAD Ta:25°C	4.68V- 5.58 V/ 230VAC 4.68V- 5.58 V/ 115VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: -2 %- 2 % (Max)	I/P: 176 VAC / 264 VAC O/P:FULL/ 0 % LOAD Ta:25°C	V1: 0.3 %- -0.3 %	P
4	LINE REGULATION	V1: -0.5 %- 0.5 % (Max)	I/P: 176 VAC ~ 264 VAC O/P:FULL LOAD Ta:25°C	V1: 0.2 %- -0.2 %	P
5	LOAD REGULATION	V1: -1 %- 1 % (Max)	I/P:230 VAC O/P:FULL -MIN LOAD Ta:25°C	V1: 0.3 %- -0.3 %	P
6	SET UP TIME	230 VAC/800 ms (Max) 115 VAC/1200 ms (Max)	I/P:230 VAC I/P:115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 524 ms 115VAC/ 377 ms	P
7	RISE TIME	230 VAC/20 ms (Max) 115 VAC/30 ms (Max)	I/P:230 VAC I/P:115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 2 ms 115VAC/ 2 ms	P
8	HOLD UP TIME	230 VAC/ 28 ms (TYP) 115 VAC/ 20 ms (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 37 ms 115VAC/ 11.6 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: < 5 %	P
10	DYNAMIC LOAD	V1: 1000 mVp-p	I/P: 230 VAC O/P:FULL /Min LOAD 90%DUTY/1KHZ Ta:25°C	196 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	176VAC~ 264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	120 V~ 264 V	P
			I/P: LOW-LINE-3V= 173 V HIGH-LINE+15%= 300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST: OK	
2	INPUT FREQUENCY RANGE	47 HZ ~ 63 HZ NO DAMAGE OSC	I/P: 176 VAC ~ 264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	EFFICIENCY	78 % (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	79.1 %	P
4	INPUT CURRENT	230 V/ 2 A (TYP) 115 V/ 3 A (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 1.5 A/ 230 VAC I = 2.6 A/ 115 VAC	P
5	INRUSH CURRENT	230 V/ 40 A (TYP) COLD START	I/P:230 VAC O/P:FULL LOAD Ta:25°C	I = 35 A/ 230 VAC	P
6	LEAKAGE CURRENT	< 2 mA / 240 VAC	I/P:254 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.5 mA N-FG: 0.4 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110 %~ 150 %	I/P: 230 VAC I/P: 115 VAC O/P: TESTING Ta:25°C	115 %/ 230 VAC 114 %/ 115 VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH1: 5.75 V~ 6.75 V	I/P: 230 VAC I/P: 115 VAC O/P: MIN LOAD Ta:25°C	5.9 V/ 230 VAC 5.9 V/ 115 VAC Hiccup Model	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: Full LOAD Ta:25°C	NO DAMAGE Hiccup Mode	P

ENVIRONMENT TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : RS-150-5 1. ROOM AMBIENT BURN-IN : 1 HRS I/P: 230 VAC O/P: FULL LOAD Ta= 27.2 °C 2. HIGH AMBIENT BURN-IN : 3 HRS I/P: 230 VAC O/P: FULL LOAD Ta= 43.4 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P: 230 VAC O/P: 117%LOAD Ta:25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P: 230 VAC O/P: 100% LOAD Ta= -25 °C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 40°C NO DAMAGE	I/P: 272 VAC O/P:FULL LOAD Ta= 40°C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.03 %(0-50°C)	I/P: 230 VAC O/P:FULL LOAD	± 0.01 %(0-50°C)	P
6	VIBRATION TEST	1 Set Operating at I/P: 230 VAC NO LOAD (1) Waveform: Sine Wave (2) Frequency:10-500Hz (3) Sweep Time:10min/sweep cycle (4) Acceleration:5G (5) Test Time:1 hour in each axis (X.Y.Z) (6) Ta:25°C		TEST : OK	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min I/P-FG: 2 KVAC/min O/P-FG: 0.5 KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 2.4 KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 4.33 mA I/P-FG: 3.36 mA O/P-FG: 2.67 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 9 G Ω I/P-FG: 7 G Ω O/P-FG: 12 G Ω NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	30 A / 2min Ta:25°C	7 mΩ	P
4	APPROVAL	TUV: Certificate NO : R50046942 UL: File NO : E183223			P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT: 2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

**M.T.B.F & LIFE CYCLE CALCULATION**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	RS-150-5 : SUPPOSE C64 IS THE MOST CRITICAL COMPONENT I/P: 230 VAC O/P:FULL LOAD Ta= 25 °C LIFE TIME= 63770 HRS I/P: 230 VAC O/P:FULL LOAD Ta= 40 °C LIFE TIME= 33224 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 244K HRS			P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated 2SK2082 : 800V / 9 A	I/P:High-Line +3V =267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 536 V (2) 678 V (3) 680 V	P
2	Diode Peak Voltage	D60 Rated D83-004 : 40 V / 30 A	I/P:High-Line +3V =267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 24.7 V (2) 24.5 V (3) 24.7 V	P
3	Clamp Diode Peak Voltage	D1 Rated HER208 :1K V / 2 A	I/P:High-Line +3V =267 V O/P: (1)Full Load (2) Dynamic Load 90%Duty/1KHz Ta:25°C	(1) 666 V (2) 664 V	P
4	Input Capacitor Voltage	C5 Rated : 330u /200 V	I/P:High-Line +3V =267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 187 V (2) 184 V (3) 184 V	P
5	Control IC Voltage Test	U1 Rated 1203 : 16 V	I/P:High-Line +3V =267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 14.9 V (4) 14.9 V (5) 14.9 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2004/3/19	RD SAMPLE	PASS	VINCENT TSENG	MAX LIN
2004/7/8	PRODUCT SAMPLE A404B34	PASS	VINCENT TSENG	MAX LIN
2004/8/30	PRODUCT SAMPLE A408B09	PASS	VINCENT TSENG	MAX LIN

2003/12/12 A50-F023