

MODEL : NED-100C

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 120 mVp-p (Max) V2: 80 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 19 mVp-p V2: 23 mVp-p	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1:11.4V ~13.2 V	I/P: 230 VAC I/P:115VAC O/P:MIN LOAD Ta:25°C	9.211V~13.746 V /230vAC 9.358V~13.762V/115VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: -2 %~ +2% (Max) V2: -3 %~ +3% (Max)	I/P:200VAC / 264 VAC O/P:FULL/ 0 % LOAD Ta:25°C	V1: 0.36 %~ 0.47% V2:0.86 %~1.74 %	P
4	LINE REGULATION	V1: -0.5 %~+0.5 % (Max) V2: -0.5 %~+0.5 % (Max)	I/P: 200 VAC ~ 264VAC O/P:FULL LOAD Ta:25°C	V1: -0.05%~ 0 % V2: 0 %~ 0 %	P
5	LOAD REGULATION	V1: -1%~ 1 % (Max) V2: -2%~ 2 % (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: -0.05 %~ 0 % V2:0.24 %~ 0.49 %	P
6	SET UP TIME	230VAC/ 2000 ms (Max) 115VAC/ 1200 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/1424.671ms 115 VAC/905.873ms	P
7	RISE TIME	230VAC/ 30 ms (Max) 115VAC/ 30 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/7.813 ms 115 VAC/ 7.774 ms	P
8	HOLD UP TIME	230VAC/25 ms (TPY) 115VAC/20 ms (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/31.216ms 115 VAC/28.328 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: 4.17 %	P
10	DYNAMIC LOAD	V1: 1200 mVp-p	I/P: 230 VAC O/P(1)FULL /Min LOAD 90%DUTY/1KHZ (2)50% /Min LOAD 90%DUTY/1KHZ Ta:25°C	306mVp-p 158mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	176AC~264VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	134.112V~264 V	P
			I/P: LOW-LINE-3V= 173V HIGH-LINE+15%= 300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST: OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 200 VAC ~264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	EFFICIENCY	80 % (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	82.97%	P
4	INPUT CURRENT	230 V/ 1.2A (Typ) 115 V/ 2 A (Typ)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 0.938A/ 230VAC I =1.748 A/ 115VAC	P
5	INRUSH CURRENT	230 V/45 A (Typ) COLD START	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	I =38.601A/ 230VAC	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110%~150% RATED OUTPUT POWER	I/P: 230 VAC/115VAC O/P:TESTING Ta:25°C	140%/230VAC 140%/ 115VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH1: 13.8V~15.8V	I/P: 230 VAC/115VAC O/P:MIN. LOAD Ta:25°C	14.521V/230VAC 14.520V/115VAC Hiccup Model	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup Mode	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min I/P-FG:2 KVAC/min O/P-FG:0.5KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 2.4 KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P:9.02 mA I/P-FG:7.35mA O/P-FG:9.61 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P:2.02 G Ω I/P-FG:G 1.13Ω O/P-FG:3.08G Ω NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40A / 2min Ta:25°C	7 mΩ	P
4	LEAKAGE CURRENT	< 2mA / 240VAC	I/P: 264 VAC O/P:Min LOAD Ta:25°C	L-FG: 1.35 mA N-FG: 1.4 mA	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230 VAC/50HZ O/P:100% LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P: 230 VAC/50HZ O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N :1KV L,N-PE:2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : NED-100C 1. ROOM AMBIENT BURN-IN : 1.5 HRS I/P: 230 VAC O/P: FULL LOAD Ta= 33.8 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P: 230 VAC O/P: FULL LOAD Ta= 36.9 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P: 230 VAC O/P: 120% LOAD Ta:25°C	TEST : OK	
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P: 230 VAC O/P: 70 % LOAD Ta= -20 °C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL °C NO DAMAGE	I/P: 277 VAC O/P: FULL LOAD Ta= 45 °C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.03 %(0-50°C)	I/P: 230 VAC O/P: FULL LOAD	± 0.01 %(0-50°C)	P
6	VIBRATION TEST	1 Carton & 1 Set Operating at I/P: VAC NO LOAD (1) Waveform: Sine Wave (2) Frequency: 10~500Hz (3) Sweep Time: 10min/sweep cycle (4) Acceleration: 2G (5) Test Time: 1 hour in each axis (X.Y.Z) (6) Ta: 25°C		TEST : OK	P

M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	NED-100C: SUPPOSE C105 IS THE MOST CRITICAL COMPONENT I/P: 230 VAC O/P: FULL LOAD Ta= 25 °C LIFE TIME= 98617 HRS I/P: 230 VAC O/P: FULL LOAD Ta= 45 °C LIFE TIME= 27936 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 320.7K HRS			P



COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated 900V 7A	I/P:High-Line +3V = 267 V O/P: (1)Full Load input on/off (2)Output Short Ta:25°C	(1)800V (2)856 V	P
2	Diode Peak Voltage	D100 Rated 200V 30 A	I/P:High-Line +3V = 267 V O/P: (1)Full Load input on/off (2)Output Short Ta:25°C	(1)83.6V (2)85.2V	p
3	Input Capacitor Voltage	C 5 Rated 220 uF /250 V	I/P:High-Line +3V =267 V O/P: (1)Full Load input on/off (2) Min load input on /Off Ta:25°C	(1)183V (2)180V	P
4	Control IC Voltage Test	U1 Rated 30 V	I/P:High-Line +3V =267 V O/P:(1) Output Short (2)O.L.P Ta:25°C	(1)20.5V (2) 20.3V	P

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	DANIEL GAO	SANFORD SU	VINCENT ZENG

12.10.30 A50-F031