



Test Report: HSN-200-4.2B

200W Single Output Switching Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 150 mVp-p (Max)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	V1 : 102 mVp-p (Max)	PASS
2	OUTPUT VOLTAGE ADJUST RANGE	V1 : 3.6 V ~ 4.4 V	I/P : 230 VAC O/P : NO LOAD Ta : 25°C	V1 : 3.486V~ 4.494V / 230 VAC	PASS
3	OUTPUT VOLTAGE TOLERANCE	V1 : -2%~ 2% (Max)	I/P : 180 VAC / 264 VAC O/P : FULL/ NO LOAD Ta : 25°C	V1 : -0.326 %~ 0.591 %	PASS
4	LINE REGULATION	V1 : -0.5%~ 0.5% (Max)	I/P : 180 VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : -0.005 %~ 0.005 %	PASS
5	LOAD REGULATION	V1 : -2%~ 2% (Max)	I/P : 230 VAC O/P : FULL~NO LOAD Ta : 25°C	V1 : -0.326 %~ 0.326 %	PASS
6	SET UP TIME	230VAC : 1500 ms (Max)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 1041 ms	PASS
7	RISE TIME	230VAC : 100 ms (Max)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 4.40 ms	PASS
8	HOLD UP TIME	230VAC : 20 ms (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 27.1 ms	PASS
9	OVER/UNDERSHOOT TEST	< ±10%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : < ±10 %	PASS
10	DYNAMIC LOAD	V1 : 840 mVp-p	I/P : 230 VAC (1).O/P : FULL /NO LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /NO LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 480 mVp-p (2) 675 mVp-p	PASS

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	180 VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	177 V~264 V	PASS
			I/P : (1)LOW-LINE-3V=177 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec OFF : 30 Sec 10MIN (2)230Vac ON : 0.5 Sec OFF : 0.5 Sec 20MIN (3)230Vac ON : 3Sec OFF : 3Sec 12HOURS (POWER ON/OFF NO DAMAGE)	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 180 VAC ~ 264 VAC O/P : FULL ~NO LOAD Ta : 25°C	TEST : OK	PASS
3	EFFICIENCY	88% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	88.11%	PASS
4	INPUT CURRENT	230V/ 2.5 A (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 1.4 A/ 230 VAC	PASS
5	INRUSH CURRENT	230V/ 80 A (TYP) Twidth =1000 us measured at 50% Ipeak COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 77.64 A	PASS
6	LEAKAGE CURRENT	< 1 mA	I/P : 264 VAC O/P : NO LOAD Ta : 25°C	L-CASE : 0.555 mA N-CASE : 0.549 mA	PASS

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 % ~ 140 %	I/P : 200 VAC I/P : 230 VAC I/P : 264 VAC O/P : TESTING Ta : 25°C	122.0 %/ 200 VAC 123.3 %/ 230 VAC 124.3 %/ 264 VAC Hiccup mode,recovers automatically after fault condition is removed	PASS
2	OVER VOLTAGE PROTECTION	CH1 : 4.6 V ~ 5.4 V	I/P : 180 VAC I/P : 230 VAC I/P : 264 VAC O/P : NO LOAD Ta : 25°C	5.071 V/ 180 VAC 5.052 V/ 230 VAC 5.041 V/ 264 VAC Hiccup mode,recovers automatically after fault condition is removed	PASS
3	OVER TEMPERATURE PROTECTION	SPEC : O.T.P. NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down	PASS
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup mode,recovers automatically after fault condition is removed.	PASS

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q2 Rated 600 V 11A	I/P : High-Line +3V = 267 V O/P : (1)FULL LOAD Turn on (2) Output Short (3) FULL LOAD continue Ta : 25°C	(1) 408 V (2) 396 V (3) 374 V	PASS
2	Diode Peak Voltage	Q100 Rated 40 V 32 A Q102 Rated 40 V 120 A	I/P : High-Line +3V = 267 V O/P : (1) FULL LOAD Turn on (2)Output Short (3) FULL LOAD continue Ta : 25°C	(1) 22.8 V (2) 21.8 V (3) 22.8 V (1) 22.8 V (2) 21.8 V (3) 22.4 V	PASS
3	Input Capacitor Voltage	C5 Rated 330uF / 200 V	I/P : High-Line +3V = 267 V O/P : (1) FULL LOAD Turn on /Off (2) NO load Turn on /Off (3) FULL LOAD /Min load Change Ta : 25°C	(1) 191 V (2) 186 V (3) 190 V	PASS
4	Control IC Voltage Test	U1 Rated 30V	I/P : High-Line +3V = 267 V O/P : (1) FULL LOAD Turn on /Off (2) NO load Turn on /Off (3) FULL LOAD /Min load Change Ta : 25°C	(1) 20.2 V (2) 21.6 V (3) 20.6 V	PASS

SAFETY TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min I/P-FG : 2 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P : 3.6 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 2.189 mA I/P-FG : 2.387 mA O/P-FG : 1.382 mA NO DAMAGE	PASS
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : > 9999MΩ I/P-FG : > 9999MΩ O/P-FG : > 9999MΩ NO DAMAGE	PASS
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40A / 2min Ta : 25°C	13 mΩ	PASS

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT																																																																																								
1	TEMPERATURE RISE TEST	MODEL : HSN-200-4.2B 1. ROOM AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=32.2 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=56.5 °C			PASS																																																																																								
		<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta= 32.2°C</th> <th>HIGH AMBIENT Ta= 56.5 °C</th> </tr> </thead> <tbody> <tr><td>1</td><td>ZNR1</td><td>45.5°C</td><td>73.1°C</td></tr> <tr><td>2</td><td>RTH1</td><td>93.5°C</td><td>110.1°C</td></tr> <tr><td>3</td><td>C5</td><td>56.7°C</td><td>82.4°C</td></tr> <tr><td>4</td><td>Q1</td><td>57.8°C</td><td>87.3°C</td></tr> <tr><td>5</td><td>Q2</td><td>56.5°C</td><td>85.5°C</td></tr> <tr><td>6</td><td>D6</td><td>69.7°C</td><td>98.4°C</td></tr> <tr><td>7</td><td>C36</td><td>62.6°C</td><td>91.4°C</td></tr> <tr><td>8</td><td>R18</td><td>80.5°C</td><td>109.3°C</td></tr> <tr><td>9</td><td>T1</td><td>87.7°C</td><td>115.2°C</td></tr> <tr><td>10</td><td>C166</td><td>65.8°C</td><td>92.3°C</td></tr> <tr><td>11</td><td>C165</td><td>67.3°C</td><td>93.8°C</td></tr> <tr><td>12</td><td>Q102</td><td>61.7°C</td><td>89.7°C</td></tr> <tr><td>13</td><td>Q103</td><td>54.4°C</td><td>82.6°C</td></tr> <tr><td>14</td><td>C105</td><td>57.6°C</td><td>84.4°C</td></tr> <tr><td>15</td><td>C107</td><td>60.9°C</td><td>88.0°C</td></tr> <tr><td>16</td><td>L100</td><td>75.5°C</td><td>102.5°C</td></tr> <tr><td>17</td><td>Q100</td><td>75.8°C</td><td>96.0°C</td></tr> <tr><td>18</td><td>Q101</td><td>85.6°C</td><td>111.6°C</td></tr> <tr><td>19</td><td>U1</td><td>53.3°C</td><td>81.2°C</td></tr> <tr><td>20</td><td>TSW1</td><td>64.4°C</td><td>92.0°C</td></tr> <tr><td>21</td><td>TC</td><td>48.0°C</td><td>76.2°C</td></tr> </tbody> </table>	NO	Position		ROOM AMBIENT Ta= 32.2°C	HIGH AMBIENT Ta= 56.5 °C	1	ZNR1	45.5°C	73.1°C	2	RTH1	93.5°C	110.1°C	3	C5	56.7°C	82.4°C	4	Q1	57.8°C	87.3°C	5	Q2	56.5°C	85.5°C	6	D6	69.7°C	98.4°C	7	C36	62.6°C	91.4°C	8	R18	80.5°C	109.3°C	9	T1	87.7°C	115.2°C	10	C166	65.8°C	92.3°C	11	C165	67.3°C	93.8°C	12	Q102	61.7°C	89.7°C	13	Q103	54.4°C	82.6°C	14	C105	57.6°C	84.4°C	15	C107	60.9°C	88.0°C	16	L100	75.5°C	102.5°C	17	Q100	75.8°C	96.0°C	18	Q101	85.6°C	111.6°C	19	U1	53.3°C	81.2°C	20	TSW1	64.4°C	92.0°C	21	TC	48.0°C	76.2°C		
NO	Position	ROOM AMBIENT Ta= 32.2°C	HIGH AMBIENT Ta= 56.5 °C																																																																																										
1	ZNR1	45.5°C	73.1°C																																																																																										
2	RTH1	93.5°C	110.1°C																																																																																										
3	C5	56.7°C	82.4°C																																																																																										
4	Q1	57.8°C	87.3°C																																																																																										
5	Q2	56.5°C	85.5°C																																																																																										
6	D6	69.7°C	98.4°C																																																																																										
7	C36	62.6°C	91.4°C																																																																																										
8	R18	80.5°C	109.3°C																																																																																										
9	T1	87.7°C	115.2°C																																																																																										
10	C166	65.8°C	92.3°C																																																																																										
11	C165	67.3°C	93.8°C																																																																																										
12	Q102	61.7°C	89.7°C																																																																																										
13	Q103	54.4°C	82.6°C																																																																																										
14	C105	57.6°C	84.4°C																																																																																										
15	C107	60.9°C	88.0°C																																																																																										
16	L100	75.5°C	102.5°C																																																																																										
17	Q100	75.8°C	96.0°C																																																																																										
18	Q101	85.6°C	111.6°C																																																																																										
19	U1	53.3°C	81.2°C																																																																																										
20	TSW1	64.4°C	92.0°C																																																																																										
21	TC	48.0°C	76.2°C																																																																																										
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/200VAC O/P : FULL LOAD Ta= -30°C	TEST : OK	PASS																																																																																								
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 50 °C HUMIDITY= 95% R.H	TEST : OK	PASS																																																																																								
4	TEMPERATURE COEFFICIENT	±0.03 %(0~60°C)	I/P : 230 VAC O/P : FULL LOAD	±0.01 %(0~60°C)	PASS																																																																																								
5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	PASS																																																																																								

6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C~ +55°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/FULL LOAD AC ON/OFF TEST turn on 58sec ; turn off 2sec	OK	PASS
7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 4G (5) Test Time : 90min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	PASS
8	CAPACITOR LIFE CYCLE	HSN-200-4.2B: SUPPOSE C107 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=50 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta=50 °C LIFE TIME	(1) 413586 HRS (2) 60231 HRS (3) 104164 HRS (4) 178803 HRS	PASS
9	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 283.069KHS		PASS
10	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 20000 hours @ Tcase 80°C		PASS

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	ZHANGZJ/ZHUOKB	SKY	LIUWY