



Test Report: HBG-160P-60

160W Constant Voltage + Constant Current LED Driver

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 300 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 60 mVp-p (Max)	P
2	CONSTANT CURRENT REGION	CH1: 36 V ~ 60 V	I/P : 230VAC O/P : CV MODE Ta : 25°C	O/P= 36V : 2.616 A O/P= 60 V : 2.626 A	P
3	CURRENT ADJUST RANGE	CH1: 1.6 A ~ 2.6 A	I/P : 230VAC I/P : 115VAC O/P : CV MODE Ta : 25°C	1.447 A ~ 2.892 A /230VAC 1.448 A ~ 2.592 A /115VAC	P
4	OUTPUT VOLTAGE TOLERANCE	V1 : 2%~ -2% (Max)	I/P : 100 VAC / 305 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.645 %~ -0.208 %	P
5	LINE REGULATION	V1 : 0.5%~ -0.5% (Max)	I/P : 100 VAC ~ 305 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~ 0 %	P
6	LOAD REGULATION	V1 : 1%~ -1% (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.041 %~ -0.051 %	P
7	SET UP TIME	230VAC : 500 ms (Max) 115VAC : 2500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 229.848 ms 115VAC/ 420.686 ms	P
8	RISE TIME	230VAC : 200 ms (Max) 115VAC : 200 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 34.95 ms 115VAC/ 34.70 ms	P
9	HOLD UP TIME	230VAC : 12 ms (TYP) 115VAC : 12 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 22.56 ms 115VAC/ 22.67 ms	P
10	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
11	DYNAMIC LOAD	V1 : 6000 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 350 mVp-p (2) 2470 mVp-p	P

12	DIMMING TEST (B-TYPE)	SPEC:										
		*Output constant current level can be adjusted by applying one of the three methodologies between DIM+ and DIM-: 1 ~ 10Vdc, or 10V PWM signal or resistance.										
		*Reference resistance value for output current adjustment (Typical)										
		Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		*1 ~ 10V dimming function for output current adjustment (Typical)										
		Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		*10V PWM signal for output current adjustment (Typical) Frequency range : 100Hz~3KHz										
		Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		TEST RESULT: I/P : 230 VAC ; Ta : 25°C										
1	Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K	
	Output current	0.244A	0.511A	0.781A	1.045A	1.312A	1.582A	1.853A	2.125A	2.399A	2.644A	
	%	9.38%	19.65%	30.04%	40.19%	50.46%	60.85%	71.27%	81.73%	92.27%	101.7%	
2	Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V	
	Output current	0.249A	0.510A	0.770A	1.029A	1.287A	1.548A	1.806A	2.069A	2.330A	2.588A	
	%	9.58%	19.62%	29.62%	39.58%	49.50%	59.54%	69.46%	79.58%	89.62%	99.54%	
3	Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
	Output current	0.270A	0.530A	0.794A	1.049A	1.307A	1.565A	1.823A	2.083A	2.342A	2.583A	
	%	10.38%	20.38%	30.54%	40.35%	50.27%	60.19%	70.12%	80.12%	90.08%	99.35%	

P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~305 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	87 V~305V	P
			I/P : LOW-LINE-3V=97 V HIGH-LINE=305 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100 VAC ~ 305 VAC O/P : FULL~MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.98 / 115 VAC(TYP) 0.92 / 277 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC I/P : 277 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.971 / 230 VAC PF= 0.996 / 115 VAC PF= 0.947 / 277 VAC	P
4	EFFICIENCY	93.5 % (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	93.65 %	P
5	INPUT CURRENT	230V/ 0.78 A (TYP) 115V/ 1.70 A (TYP) 277V/ 0.70 A (TYP)	I/P : 230 VAC I/P : 115 VAC I/P : 277 VAC O/P : FULL LOAD Ta : 25°C	I= 0.748 A/ 230 VAC I= 1.494 A/ 115 VAC I= 0.635 A/ 277 VAC	P
6	INRUSH CURRENT	230V/ 65 A (TYP) COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I= 55.65 A/ 230 VAC	P
7	LEAKAGE CURRENT	< 0.75 mA/ 277 VAC	I/P : 277 VAC O/P : Min LOAD Ta : 25°C	L-CASE : 0.3277 mA N-CASE : 0.3394 mA	P
8	TOTAL HARMONIC DISTORTION	Total harmonic distortion will be lower than 20% when output loading is 60% or higher at 115VAC/230VAC	I/P : 115VAC I/P : 230VAC O/P : 60% LOAD	THD : 8.33 %/115VAC THD : 12.58 %/230VAC	P
		Total harmonic distortion will be lower than 20% when output loading is 75% or higher at 277VAC	I/P : 277VAC O/P : 75% LOAD	THD : 13.71 %/277VAC	

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	95 % ~ 108 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	100.98 %/ 230 VAC 101.04 %/ 115 VAC Constant current limiting, recovers automatically after fault condition is removed.	P
2	OVER VOLTAGE PROTECTION	CH1 : 65 V ~ 75 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	70.1 V/ 230 VAC 70.1 V/ 115 VAC Shut down o/p voltage with auto-recovery or re-power on to recover	P
3	OVER TEMPERATURE PROTECTION	NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage, recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 305 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup mode, recovers automatically after fault condition is removed.	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q6 Rated : 600V/11A	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 476 V (2) 450 V (3) 456 V	P
2	Diode Peak Voltage	D100 Rated : 150V/30A	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 132 V (2) 11.2 V (3) 133 V	P
3	Input Capacitor Voltage	C5 Rated : 82u/450V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 446 V (2) 442 V (3) 442 V	P
4	Control IC Voltage Test	U 2 Rated : 16V (MAX)	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 13.9 V (2) 13.8 V (3) 13.9 V	P
5	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated : 600V/16A	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 494 V (2) 454 V (3) 470 V	P

■ SAFETY & E.M.C. TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3.75 KVAC/min I/P-FG : 2.0 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P : 4.2 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 2.987 mA I/P-FG : 2.838 mA O/P-FG : 3.672 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C/70%RH	I/P-O/P : >9999 MΩ I/P-FG : >9999 MΩ O/P-FG : >9999 MΩ NO DAMAGE	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS C	I/P:220VAC/230VAC/240VAC50HZ O/P:100%,75%,60%LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55015	I/P: 230 VAC (50HZ)/115V[60HZ] O/P:FULL/65% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55015	I/P: 230 VAC (50HZ)/115V[60HZ] O/P: FULL/65% LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N- EARTH:4KKV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

■ **RELIABILITY TEST**

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : HBG-160P-48 1. ROOM AMBIENT BURN-IN : 1.0 HRS I/P : 230VAC O/P : 95% LOAD Ta=31.3 °C 2. HIGH AMBIENT BURN-IN : 2.0 HRS I/P : 230VAC O/P : 95% LOAD Ta=48.3 °C			P
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 305VAC/100VAC O/P : 95 % LOAD Ta= -45/-35°C	TEST : OK	P
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 45 °C NO DAMAGE	I/P : 305 VAC O/P : 95% LOAD Ta= 45 °C HUMIDITY= 95 %R.H	TEST : OK	P
4	TEMPERATURE COEFFICIENT	±0.03 %(0~45°C)	I/P : 230 VAC O/P : 95% LOAD	±0.005 %(0~45°C)	P
5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C ~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P
6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -45°C ~ +50°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK	P



7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 72min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
8	CAPACITOR LIFE CYCLE	HBG-160P-48:SUPPOSE C102 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=45 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=45 °C LIFE TIME	(1) 430372 HRS (2) 161982 HRS (3) 209540 HRS	P
9	MTBF	Conducted by Parts Stress Analysis Prediction 195.5K hrs min. MIL-HDBK-217F (25 °C)		P

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	ZHANGZJ/ZHOUB	SKY	LIUWY

2009/08/04 A50-G058