



# Test Report: OWA-90U-42

---

90W Single Output Switching Power Supply

## ■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

## ■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

## ■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 250 mVp-p (Max)	I/P : 230VAC O/P : 95% LOAD Ta : 25°C	V1 : 60 mVp-p (Max)	PASS
2	CONSTANT CURRENT REGION	V1 : 25.2 V ~ 42 V	I/P : 230VAC O/P : LED MODE Ta : 25°C	O/P= 41V : 2.175 A O/P= 25.2V : 2.167 A	PASS
3	OUTPUT VOLTAGE TOLERANCE	V1 : -1%~ 1% (Max)	I/P : 100 VAC / 264 VAC O/P : 95%/ NO LOAD Ta : 25°C	V1 : -0.073 %~ 0.767 %	PASS
4	LINE REGULATION	V1 : -0.5%~ 0.5% (Max)	I/P : 100 VAC ~ 264 VAC O/P : 95% LOAD Ta : 25°C	V1 : -0.073 %~ 0 %	PASS
5	LOAD REGULATION	V1 : -0.5%~ 0.5% (Max)	I/P : 230 VAC O/P : 95%-NO LOAD Ta : 25°C	V1 : -0.028 %~ 0.028 %	PASS
6	SET UP TIME	230VAC : 500 ms (Max) 115VAC : 500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : 95% LOAD Ta : 25°C	230VAC/ 321.579 ms 115VAC/ 327.960 ms	PASS
7	RISE TIME	230VAC : 80 ms (Max) 115VAC : 80 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : 95% LOAD Ta : 25°C	230VAC/ 26.981 ms 115VAC/ 33.570 ms	PASS
8	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 21.377 ms 115VAC/ 20.387 ms	PASS
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : 95% LOAD Ta : 25°C	TEST : < 5 %	PASS
10	DYNAMIC LOAD	V1 : 4200 mVp-p	I/P : 230 VAC (1).O/P : 95% /NO LOAD 90%DUTY/ 1KHZ (2).O/P : 95% /NO LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 444 mVp-p (2) 832 mVp-p	PASS

**INPUT FUNCTION TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264 VAC	I/P : TESTING O/P : 95% LOAD Ta : 25°C	87 V~264V	PASS
			I/P : LOW-LINE=3V=87 V HIGH-LINE=264 V O/P : 95%/NO LOAD ON : 30 Sec . OFF : 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 90 VAC ~ 264 VAC O/P : 95% ~NO LOAD Ta : 25°C	TEST : OK	PASS
3	POWER FACTOR	0.96 / 230 VAC(TYP) 0.98 / 115 VAC(TYP)	I/P : 230 VAC	PF= 0.976 / 100%	PASS
			I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.997 / 100%	
4	EFFICIENCY	91% / 230 VAC(TYP) 89.5% / 115 VAC(TYP)	I/P : 230 VAC	91.20% / 230VAC	PASS
			I/P : 115 VAC O/P : 95% LOAD Ta : 25°C	90.29% / 115VAC	
5	INPUT CURRENT	230V/ 0.5 A (TYP) 115V/ 0.95 A (TYP)	I/P : 230 VAC	I = 0.439 A/ 230 VAC	PASS
			I/P : 115 VAC O/P : 95% LOAD Ta : 25°C	I = 0.876 A/ 115 VAC	
6	INRUSH CURRENT	230V/ 60 A (TYP) 115V/ 30 A (TYP) Twidth =550 us measured at 50% Ipeak COLD START	I/P : 230 VAC	I = 57.281 A/ 230 VAC	PASS
			I/P : 115 VAC O/P : 95% LOAD Ta : 25°C	I = 26.000 A/ 115 VAC  Twidth = 448 us	
7	LEAKAGE CURRENT	< 0.25 mA/ 240 VAC < 0.125 mA/ 120 VAC	I/P : 240 VAC	L-CASE : 0.002 mA/240VAC	PASS
			I/P : 120 VAC O/P : NO LOAD Ta : 25°C	N-CASE : 0.002 mA/240VAC L-CASE : 0.002 mA/120VAC N-CASE : 0.002 mA/120VAC	
8	NO LOAD POWER CONSUMPTION	< 0.15 W	I/P : 230 VAC	0.109W / 230VAC	PASS
			I/P : 115 VAC O/P : NO LOAD Ta : 25°C	0.118W / 115VAC	
9	TOTAL HARMONIC DISTORTION	Total harmonic distortion will be lower than 20% when output loading is 60% or higher at 230V/115 V	I/P : 230VAC	TDH= 11.51% /230 VAC	PASS
			I/P : 115VAC O/P : 60% LOAD Ta : 25°C	TDH= 5.35 % /115 VAC	

### PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	95 % ~ 108 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	101.48 %/ 230 VAC 101.46 %/ 115 VAC Constant current limiting ,recovers automatically after fault condition is removed	PASS
2	OVER VOLTAGE PROTECTION	CH1 : 46 V ~ 54 V	I/P : 230 VAC I/P : 115 VAC O/P : NO LOAD Ta : 25°C	50.66 V/ 230 VAC 50.61 V/ 115 VAC Shut down o/p voltage, re-power on to recover	PASS
3	OVER TEMPERATURE PROTECTION	SPEC : O.T.P. NO DAMAGE	I/P : 230 VAC O/P : 95% LOAD	O.T.P. Active Shut down o/p voltage, re-power on to recover	PASS
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : 95% LOAD Ta : 25°C	NO DAMAGE Hiccup mode, recovers automatically after fault condition is removed.	PASS

### COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor ( D to S) or (C to E) Peak Voltage	Q2 Rated 800 V 9.0A	I/P : High-Line +3V = 267 V O/P : (1)95% Load Turn on (2) Output Short (3) 95% load continue Ta : 25°C	(1) 716 V (2) 492 V (3) 704 V	PASS
2	Diode Peak Voltage	Q101 Rated 150 V 20 A	I/P : High-Line +3V = 267 V O/P : (1) 95% Load Turn on (2)Output Short (3) 95% load continue Ta : 25°C	(1) 137 V (2) 84.0 V (3) 134 V	PASS
3	Input Capacitor Voltage	C5 Rated 82uF / 450 V	I/P : High-Line +3V = 267 V O/P : (1) 95% Load Turn on /Off (2) NO load Turn on /Off (3) 95% Load /Min load Change Ta : 25°C	(1) 448 V (2) 448 V (3) 449 V	PASS
4	Control IC Voltage Test	U1 Rated 28V	I/P : High-Line +3V = 267 V O/P : (1) 95% Load Turn on /Off (2) NO load Turn on /Off (3) 95% Load /Min load Change Ta : 25°C	(1) 17.3 V (2) 17.4 V (3) 17.2 V	PASS
5	Power Transistor ( D to S) or (C to E) Peak Voltage	Q1 Rated 600 V/ 10 A	I/P : High-Line +3V = 267 V O/P : (1) 95% Load Turn on (2) Output Short (3) 95% load continue Ta : 25°C	(1) 482 V (2) 408 V (3) 470 V	PASS

■ SAFETY & E.M.C. TEST

**SAFETY TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3.75 KVAC/min	I/P-O/P : 4.2 KVAC/min Ta : 25°C	I/P-O/P : 1.726 mA NO DAMAGE	PASS
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ	I/P-O/P : 500 VDC Ta : 25°C /70%RH	I/P-O/P : >9999 MΩ NO DAMAGE	PASS

**E.M.C TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS C	I/P:115VAC/230VAC O/P:95%, 60%LOAD Ta:25°C	PASS	PASS
2	CONDUCTION	FCC Part15 Class B	I/P: 230 VAC (50HZ)/115V[60HZ] O/P: 95% LOAD Ta:25°C	PASS Test by certified Lab	PASS
3	RADIATION	FCC Part15 Class B	I/P: 230 VAC (50HZ)/115V[60HZ] O/P: 95% LOAD Ta:25°C	PASS Test by certified Lab	PASS
4	Test by certified Lab & Test Report Prepare				

■ RELIABILITY TEST

**ENVIRONMENT TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : OWA-90U-48 1. ROOM AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : 95% LOAD Ta=25.6 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : 95% LOAD Ta=51.0 °C			PASS

		NO	Position	ROOM AMBIENT Ta= 25.6 °C	HIGH AMBIENT Ta= 51.0 °C		
		1	C5	59.0°C	81.5°C		
		2	C105	54.6°C	77.9°C		
		3	T1	62.6°C	85.7°C		
		4	Q1	60.4°C	84.8°C		
		5	Q2	62.6°C	87.1°C		
		6	Q101	56.7°C	81.8°C		
		7	L3	54.9°C	77.7°C		
		8	RTH1	61.1°C	82.7°C		
		9	D6	61.1°C	85.3°C		
		10	LF100	45.4°C	70.1°C		
		11	RTH2	56.1°C	78.8°C		
		12	C41	58.1°C	80.8°C		
		13	C45	58.0°C	80.7°C		
		14	C11	59.4°C	83.7°C		
		15	D5	55.1°C	79.0°C		
		16	U1	56.6°C	80.1°C		
		17	D10	64.0°C	88.4°C		
		18	BD1	58.1°C	82.8°C		
		19	Tc	54.0°C	79.4°C		
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR		I/P : 264VAC/100VAC O/P : 95% LOAD Ta= -40/-25°C	TEST : OK	PASS	
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE		I/P : 272 VAC O/P : 95% LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK	PASS	
4	TEMPERATURE COEFFICIENT	±0.03 %(0~50°C)		I/P : 230 VAC O/P : 95% LOAD	±0.005 %(0~50°C)	PASS	
5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC			OK	PASS	
6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -45°C~ +55°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/95% Load AC ON/OFF TEST turn on 58sec ; turn off 2sec			OK	PASS	
7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 5G (5) Test Time : 72min in each axis (X.Y.Z) (6) Ta : 25°C			TEST : OK	PASS	



8	CAPACITOR LIFE CYCLE	OWA-90U-48: SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : 95% LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : 95% LOAD Ta=50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=50 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta=50 °C LIFE TIME	(1) 289080.4 HRS (2) 59080.3 HRS (3) 85375.6 HRS (4) 99366.1 HRS	PASS
9	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 292.8 KHRS		PASS
10	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 50000 hours @ Tcase 75°C		PASS

TEST RESULT	TESTER	APPROVAL
PASS	ZHOUB/ ZHUOKB	LIUWY

2009/08/04 A50-G058